

Kamesh Bhargava Hospital And Research Centre Pvt. Ltd.

PHASE: 9, SECTOR:63
S.A.S NAGAR,
MOHALI - 160 063
Tel No. 91-79-5053207, 5053208, 5097112



Purchase Order

Supplier Code : DY-012
Store Name : General Store
Supplier Name : DYNAMIC ELECPPOWER P
Credit Period : 0 Days
Address : G-68, RIICO Industrial An
Biliya ,
City : Bhilwara, Rajasthan
Pin Code : 311 001
Phone No/Fax : 9414115151 /

Pur. Order NO : 1000307
PO Date : 12/11/16
Auth/amnd Date :

CST No. : 03242036242
TIN No. : 03242036242
PAN No. : AAACK7161P

Dear Sir/s

Ref.Your Quotation No.

Dated / /

We are pleased to place our order as under subject to the terms & conditions stated overleaf,
Kindly deliver the materials at the earliest with supporting delivery challan in QUADRUPLICATE

Sr.#	Item Code	Description	Qty.	Free	Unit	Rate	Amt.(RS)
1	EL01000564	PCC PANEL	1.00	0.00	Numb	650,722.00	650,722.00
Total							650,722.00
2	EL01000565	AC PANEL - Terrace floor	1.00	0.00	Numb	185,099.00	185,099.00
Total							185,099.00
3	EL01000566	AC Panel - 1 St Floor tarrace	1.00	0.00	Numb	191,500.00	191,500.00
Total							191,500.00
4	EL01000567	Fire fighting Panel	1.00	0.00	Numb	150,300.00	150,300.00
Total							150,300.00
5	EL01000568	Plumbing Panel	1.00	0.00	Numb	72,300.00	72,300.00
Total							72,300.00

Supplier Code : DY-012

Pur. Order NO : 1000307

Sr.#	Item Code	Description	Qty.	Free	Unit	Rate	Amt.(RS)
6	EL01000569	AHU System Panel - O.T Area	1.00	0.00	Numb	41,000.00	41,000.00
Total							41,000.00
7	EL03000559	Providing & Fixing of Push button Station	1.00	0.00	Numb	5,000.00	5,000.00
Total							5,000.00
							1,295,921.00
Other Addition (+)							0.00
Other Deduction (-)							0.00
* Net Amount (RS.)							1,295,921.00
* Incl. of all taxes							

Delivery On or before 12/11/2016
Indent (S) Processed :- 1000354,1000354,1000354

Warranty

- 1 . 24 months from the date of Commissioning

Terms of Paymen

- 2 . 30% Advance against Corporate Guarantee and 10% PBG for release of 70% payment before Dispatch

Other Terms

- 3 . LD @ 0.5% for the delay of a week or thereof, uptill max of 5% of the total order value is acceptable
- 4 . Invoice to : Shalby Ltd, Phse 9 ,Sector 63 ,S.A.S Nagar ,Mohali-160063
- 5 . Ship to : Shalby Ltd, Phse 9 ,Sector 63 ,S.A.S Nagar ,Mohali-160063
- 6 . Packing Forwarding Charges Inclusive
- 7 . TAX : VAT 5% Exclusive in the Rates
- 8 . TAX : Excise Duty : 12.5% Exclusive in the Rates
- 9 . TAX : Service Tax Inclusive in the rates
- 10 . Freight & Insurance charges Rs 50000/- Extra
- 11 . Relocation if any is inclusive in the price
- 12 . BOQ Sprcification as per Annexure 1
- 13 . Technical Sheet for Panel As per Annexure 2
- 14 . Retrofitting charges inclusive in the price
- 15 . Unloading Charges Extra at actuals

Delivery

- 16 . For PCC Panel Delievery within 45 days balance all panels within 30 days from the date of approved drawing shall be submitted within 3 days.



Supplier Code : DY-012

Pur. Order NO : 1000307

<u>Sr.#</u>	<u>Item Code</u>	<u>Description</u>	<u>Qty.</u>	<u>Free</u>	<u>Unit</u>	<u>Rate</u>	<u>Amt.(RS)</u>
-------------	------------------	--------------------	-------------	-------------	-------------	-------------	-----------------

IMPORTANT NOTE: Kindly note that with immediate effect, you are required to send us along bill, challan and copy of our purchase order. If the goods are sent to us without all the above do refuse to accept such goods in our premises, for which you will be responsible for costs and consequences.

Any dispute, differences or claims arising out of this purchase order be subject to exclusive jurisdiction of Courts at Ahm

Prepared By

Handwritten signature
12/11
16.

comcc

Handwritten signature

12/11/16

12/11/2016

Handwritten signature

Handwritten signature

Annexure 1

Sr No	Item code	Description	Unit	Qty
1	EL01000564	PCC PANEL (SUB-STATION) as per specification and SLD	No	1
2	EL01000565	AC-PANEL - TERRACE FLOOR as per specification and SLD	No	1
3	EL01000566	AC-PANEL - 1st Floor Terrace - as per specification and SLD	No	1
4	EL01000567	FIRE FIGHTING PANEL as per specification and SLD	No	1
5	EL01000568	PLUMBING PANEL as per specification and SLD	No	1
6	EL01000569	AHU-SYSTEM PANEL - O.T AREA as per specification and SLD	No	1
7	EL03000559	Supply, installation, testing & commissioning of Wall Mounted Remote Control Manual Push-Button station, 6 No. A.C On-off, push-button with on indicator in M.S encloser, Size-500x400x150MM	No	1

↑


Technical sheet

3.1	PCC PANEL (SUB-STATION) as per specification and SLD	1	Each
	Supply, Installation, testing and commissioning of LT Panel, cubicle type, made out of 14/16 SWG CRCA sheet, totally enclosed, IP 54, free standing, floor mounting, dust and vermin proof, indoor, compartmentalised, suitable for operation on 3 phase and neutral, 415 V, 50Hz AC system with busbars extensible on both sides, making interlocking arrangement between incomers & buscoupler breakers, including internal wiring with suitable size wires/cable. Suitable for both top or bottom entry of cables, incorporating incomings' EDO (Microprocessor based) ACBs, MCCBs and bus-coupler/outgoing feeders comprising of ACBs/MCCBs complete with three phase and neutral Al. busbars duly supported and enclosed at top or bottom, earthing bus bar with earthing terminals at both ends, Multifunctional Meter with CTs of suitable rating & Selector switch. Microprocessor based protection of O/L, S/C and E/F for the ACBs and Thermal magantic realese of O/C & S/C for the MCCBs , indicating lamps for RYB/ON-OFF-Trip, push buttons, earthing & control wiring etc.The floor mounting panels shall be provided with mounting channels size 75x40x5mm. The construction of panels shall be strictly as per standard specifications. Panels shall		
	INCOMERS-1000KVA Transformer: ACB 1600 A 4Pole, Electrically Operated Drawout type (Ics=Icu value 65 KA) with	1	Nos.
	D.G. Sets Incomers- (500KVA): ACB 1000 A 4Pole, Electrically Operated Drawout type (Ics=Icu value 65 KA). with O	1	Nos.
	Electrical / Mechanically Interlocking Mechanism with PLC for safe operation of 1 No In-coming for Transformer, 2	1	Nos.
	RYB Phase Indicating lights LED type	6	Nos.
	ON-OFF-TRIP Phase Indicating lights LED type	6	Nos.
	Multifunctional Digital Meter with KW,KWHA,KVA,PF ,Volt. Amp. & Frequency Meter Make Conzerv/Schneider	2	Nos.
	UVNC Relay	2	Nos.
	Shunt Trip relay	2	Nos.
	1600/5A CI-1, 5VA Current Transformer. Make	3	Nos.
	1000/5A CI-1, 5VA Current Transformer. Make	3	Nos.
	SP MCB 2 Amp. Make Hager, schneider	12	Nos.
	Reverse Power Relay with TRIP indicator on panel door with Suitable CT	2	Nos.
	Exhaust Fan with control Switch	4	Nos.
	OUT- GOING FEEDER'S		
	MCCB 400 Amp. TPN, (Icu = Ics value 50 KA) Make Schneider MG / L&T dsine / LEGRAND	1	Nos.
	Front operated Extended Rotary Handle	1	Nos.
	Spreader Links	1	Nos.
	MCCB 315 Amp. TPN, (Icu = Ics value 50 KA) Make Schneider MG / L&T dsine / LEGRAND	1	Nos.
	Front operated Extended Rotary Handle	1	Nos.
	Spreader Links	1	Nos.
	MCCB 250 Amp. TPN, (Icu = Ics value 36 KA) Make Schneider MG / L&T dsine / LEGRAND	1	Nos.
	Front operated Extended Rotary Handle	1	Nos.
	Spreader Links	1	Nos.
	MCCB 200 Amp. TPN, (Icu = Ics value 36 KA) Make Schneider MG / L&T dsine / LEGRAND	2	Nos.
	Front operated Extended Rotary Handle	2	Nos.
	Spreader Links	2	Nos.
	MCCB 125 Amp. TPN, (Icu = Ics value 35 KA) Make Schneider MG / L&T dsine / LEGRAND	5	Nos.
	Front operated Extended Rotary Handle	5	Nos.
	Spreader Links	5	Nos.
	ON Indicating lights LED type	10	Nos.
	MCB 63 Amp. 4P, (Icu = Ics value 10 KA) Make Schneider / L&T	9	Nos.
	3. Enclosure, Bus Bar, Wiring & Accessories :		
	MS Cabinet front operated compartmentalized with Base Frame fabricated from 14/16 CRCA Sheet (make TATA Ste	1	SET
	1600Amp.TP&N Aluminium busbars(Make Hindalco) of high conductivity electrolytic quality aluminium alloy E 91 grade, 1100 Volts grade (maximum current density 1.0 A/Sq. mm) duly covered with heat shrinkable sleeves colour coded duly fixed on moulded brackets and covered allaround by insulating / CRCA sheet having no exposed portion. busbar identifications, and sheet steel enclosure etc. as required.	1	SET
	Insulator Neoprene Rubber Gaskets and Rubber Boots.	1	SET
	Hardware and Accessories, Door Hinges and Locks.	1	SET
	PVC Copper Wires (Make Polycab,2.5 Sq.mm for control) , Ferrules, Thimbles(Dowell) & Other Requ. Accessories.	1	SET

EL01000564

Technical sheet

Technical sheet			
3.2	AC-PANEL - TERRACE FLOOR as per specification and SLD	1	Each
EL01000565	INCOMERS:- MCCB 400 Amp. TPN, (Icu = Ics value 50 KA) Make Schneider MG / L&T dsine / LEGRAND	1	
	Front operated Extended Rotary Handle	1	
	Spreader Links	1	
	RYB Phase Indicating lights LED type	3	
	Multifunctional Digital Meter with Volt. Amp. & Frequency Meter Make Naptune /HPL /Conzerv/Schneider	1	
	400/5A CI-1, 5VA Current Transformer.	3	
	SP MCB 2 Amp.	3	
	Power Terminal Blocks - Stud Type.	3	
	OUT- GOING FEEDER'S		
	MCCB 80 Amp. TPN, (Icu = Ics value 25 KA) Make Schneider MG / L&T dsine / LEGRAND	6	
	MCCB 63 Amp. TPN, (Icu = Ics value 25 KA) Make Schneider MG / L&T dsine / LEGRAND	4	
	Front operated Extended Rotary Handle	10	
	Spreader Links	10	
	Contactactor 4P, 80 Amp. MCX 21	6	
	Contactactor 4P, 63 Amp. MCX 12	4	
	Single Phase Preventer	10	
	ON Indicating lights LED type	10	
	ON-OFF Push Button	20	
	Add-on Aux. Contact Block	10	
	SP MCB 2 Amp.	10	
	3. Enclosure, Bus Bar, Wiring & Accessories :		
	MS Cabinet front operated compartmentalized with Base Frame fabricated from 14/16 CRCA Sheet (make TATA Steel	1	
	500 Amp. TP&N Aluminium busbars of high conductivity electrolytic quality aluminium alloy E 91 grade, 1100 Volts grade (maximum current density 1.0 A/Sq. mm) duly covered with heat shrinkable sleeves colour coded duly fixed on moulded brackets and covered allaround by insulating / CRCA sheet having no exposed portion. busbar identifications and sheet steel enclosure etc. as required	1	
	Power & Control Wiring	12	
	Insulator Neoprene Rubber Gaskets and Rubber Boots.	1	
Hardware and Accessories, Door Hinges and Locks.	1		
PVC Copper Wires, Ferrules, Thimbles & Other Requ. Accessories.	1		
3.3	AC-PANEL - 1st Floor Terrace - as per specification and SLD	1	Each
EL01000566	INCOMERS:- MCCB 315 Amp. TPN, (Icu = Ics value 50 KA) Make Schneider MG / L&T dsine / LEGRAND	1	
	Front operated Extended Rotary Handle	1	
	Spreader Links	1	
	RYB Phase Indicating lights LED type	3	
	Multifunctional Digital Meter with Volt. Amp. & Frequency Meter Make Naptune /HPL /Conzerv/Schneider	1	
	300/5A CI-1, 5VA Current Transformer.	3	
	SP MCB 2 Amp.	3	
	Power Terminal Blocks - Stud Type.	3	
	OUT- GOING FEEDER'S		
	MCCB 80 A TPN, (Icu = Ics value 25 KA) Make Schneider MG / L&T dsine / LEGRAND	4	
	MCCB 63 A TPN, (Icu = Ics value 25 KA) Make Schneider MG / L&T dsine / LEGRAND	8	
	Front operated Extended Rotary Handle	12	
	Spreader Links	12	
	Contactactor 4P, 80 Amp. MCX 21	4	
	Contactactor 4P, 63 Amp. MCX 12	8	
	Single Phase Preventer	12	
	ON Indicating lights LED type	12	
	ON-OFF Push Button	24	
	Add-on Aux. Contact Block	12	
	SP MCB 2 Amp.	12	
	3. Enclosure, Bus Bar, Wiring & Accessories :		
	MS Cabinet front operated compartmentalized with Base Frame fabricated from 14/16 CRCA Sheet (make TATA Steel	1	
	400 Amp. TP&N Aluminium busbars of high conductivity electrolytic quality aluminium alloy E 91 grade, 1100 Volts grade (maximum current density 1.0 A/Sq. mm) duly covered with heat shrinkable sleeves colour coded duly fixed on moulded brackets and covered allaround by insulating / CRCA sheet having no exposed portion. busbar identifications and sheet steel enclosure etc. as required	1	
	Power & Control Wiring	15	
	Insulator Neoprene Rubber Gaskets and Rubber Boots.	1	
Hardware and Accessories, Door Hinges and Locks.	1		
PVC Copper Wires, Ferrules, Thimbles & Other Requ. Accessories.	1		

Technical sheet

Technical sheet				
3.5	PLUMBING PANEL as per specification and SLD	1	Each	
EL01000568	INCOMERS:- MCCB 125 Amp. 3 Pole, (Icu = Ics value 36 KA) Make Schneider MG / L&T dsine / LEGRAND	1		
	Front operated Extended Rotary Handle	1		
	Spreader Links	1		
	RYB Phase Indicating lights LED type	3		
	Multifunctional Digital Meter with Volt. Amp. & Frequency Meter Make Naptune /HPL /Conzerv/Schneider	1		
	150/5A CI-1, 5VA Current Transformer.	3		
	SP MCB 2 Amp.	3		
	Power Terminal Blocks - Stud Type.	3		
	OUT- GOING FEEDER'S			
	MCCB 63 Amp. TPN, (Icu = Ics value 36 KA) Make Schneider / L&T	2		
	Front operated Extended Rotary Handle	1		
	Spreader Links	1		
	MCB 32 Amp. 4P, 10 KA Make Schneider MG / L&T dsine / LEGRAND	1		
	MCB 25 Amp. 4P, 10 KA Make Schneider MG / L&T dsine / LEGRAND	3		
	Contractor 22 Amp. 3P A.C 3 Duty	3		
	Contractor 18 Amp. 3P A.C 3 Duty	4		
	Over load relay 15 HP star delta starter	1		
	Over load relay 5-7.5 HP DOL star delta starter	4		
	Timer	1		
	Single phase properinter	5		
	Auto Mannual Selector Switch	5		
	Amp. AM meter	1		
	On-Off indicating lights LED type	10		
	On-Off Push button	10		
	60/5A CI-1, 5VA Current Transformer.	3		
	SP MCB 2 Amp.	10		
	Power Terminal Blocks	18		
	Control Terminal Blocks	20		
	Front Add-on aux. contact block	6		
	Power and Control Wiring	6		
		3. Enclosure, Bus Bar, Wiring & Accessories :		
	MS Cabinet front operated compartmentalized with Base Frame fabricated from 14/16 CRCA Sheet (make TATA Stee	1		
	200Amp. TP&N Aluminium busbars of high conductivity electrolytic quality aluminium alloy E 91 grade, 1100 Volts grade (maximum current density 1.0 A/Sq. mm) duly covered with heat shrinkable sleeves colour coded duly fixed on moulded brackets and covered allaround by insulating / CRCA sheet having no exposed portion. busbar identifications and sheet steel enclosure etc as required.	1		
	Insulator Neoprene Rubber Gaskets and Rubber Boots.	1		
	Hardware and Accessories, Door Hinges and Locks.	1		
	PVC Copper Wires, Ferrules, Thimbles & Other Requ. Accessories.	1		
3.7	AHU-SYSTEM PANEL - O.T AREA as per specification and SLD	1	Each	
EL01000569	INCOMERS:- MCCB 200 Amp. 3 Pole, (Icu = Ics value 36 KA) Make Schneider MG / L&T dsine / LEGRAND	1		
	Front operated Extended Rotary Handle	1		
	Spreader Links	1		
	RYB Phase Indicating lights LED type	3		
	Multifunctional Digital Meter with Volt. Amp. & Frequency Meter Make Naptune /HPL /Conzerv/Schneider	1		
	200/5A CI-1, 5VA Current Transformer.	3		
	SP MCB 2 Amp.	3		
	Power Terminal Blocks - Stud Type.	3		
	OUT- GOING FEEDER'S			
	MCB 63 Amp. TPN, (Icu = Ics value 10 KA) Make Schneider / L&T	7		
		3. Enclosure, Bus Bar, Wiring & Accessories :		
		MS Cabinet front operated compartmentalized with Base Frame fabricated from 14/16 CRCA Sheet (make TATA Stee	1	
		250Amp. TP&N Aluminium busbars of high conductivity electrolytic quality aluminium alloy E 91 grade, 1100 Volts grade (maximum current density 1.0 A/Sq. mm) duly covered with heat shrinkable sleeves colour coded duly fixed on moulded brackets and covered allaround by insulating / CRCA sheet having no exposed portion. busbar identifications and sheet steel enclosure etc as required.	1	
		Insulator Neoprene Rubber Gaskets and Rubber Boots.	1	
		Hardware and Accessories, Door Hinges and Locks.	1	
		PVC Copper Wires, Ferrules, Thimbles & Other Requ. Accessories.	1	